

SURVEY NO. 2737

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250, REVISED BY CHAPTER 555, O. L. 1963

FOR - ELK LUMBER COMPANY  
P. O. BOX 606, MEDFORD, OREGON

PURPOSE - To remonument and perpetuate the section corner common to Sections 7, 8, 17 and 18, Township 32 South, Range 2 East, Willamette Meridian.

## PROCEDURE -

Found the original Southwest BT which is a dead and down Douglas fir, with scribing exposed and legible. From this tree and the record bearings and distances, identified the remains of the other original BT's which are as follow:

1. The original Northwest BT is now a decayed Douglas fir stub with all markings destroyed by fire and decay.
2. The position of the original Northeast BT is marked by Madrone sprout growth.
3. The original Southeast BT is a Ponderosa Pine stub with all markings destroyed by decay.

From this evidence and the record bearings and distances (disregarding the bearing to the Northwest BT which did not check out) set a 1 inch by 36 inch galvanized steel pipe driven 30 inches in the ground and capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1964  
T 32 S R 2 E

S 7	S 8
S 18	S 17

SEC COR  
RS 583



## NEW BEARING TREES MARKED -

- A 16 inch Douglas fir bears North 52° East 8.9 feet.
- A 13 inch Douglas fir bears South 71° East 21.0 feet.
- A 13.5 inch Douglas fir bears South 48° West 35.1 feet
- A 10 inch Incense Cedar bears North 29° West 16.0 feet.

All the new B T's are double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower.

Distances were measured to face of blaze and compass variation was set at 20° 00' East.

Field work by R. Vincent and B. Brandt, December 16, 1964.

REGISTERED  
OREGON  
LAND SURVEYOR

*Robert M. Vincent*

JULY 9, 1962  
ROBERT M. VINCENT  
583