

SURVEY NARRATIVE TO COMPLY WITH ORS 209.250, REVISED BY CHAPTER 555, O. L. 1963

FOR - ELK LUMBER COMPANY
P. O. BOX 606, MEDFORD, OREGON

PURPOSE - To remonument and perpetuate the section corner common to sections 25, 26, 35 and 36, Township 32 South, Range 1 West, Willamette Meridian.

PROCEDURE -

Found the original stone in place and the original Southwest Bearing Tree which is now an 8 inch Yew with all scribing intact. Also found the stump hole and the badly decayed trunk of the original Northwest Bearing Tree. Found no trace of the other original BT's.

Checked the position of the original stone against the record bearing and distance to the original Southwest Bearing Tree and finding it to be correct; referenced and removed said stone and replaced it with a 1 inch by 36 inch galvanized steel pipe driven 20 inches in the ground to bedrock and surrounded by a mound of stones including the original monument. Pipe monument is capped with a 1-1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown in 1/8 inch letters and numerals:

1964
T 32 S R 1 W

26	25
35	36

SEC COR
RS 583

From this monument the original 8 inch Yew BT bears South 20° West 13.0 feet.

NEW BT'S

From the above described pipe monument a 10 inch Maple, single blazed and scribed "RS 583 BT" bears North 24° East 45.1 feet; a 36 inch Douglas fir, single blazed and scribed "RS 583 BT" bears South 82° East 28.2 feet and an 11 inch Maple, double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower, bears North 25° 30' West 4.85 feet.

All distances were measured to face of blaze.

Compass variation was set at 20°00' East.

Field work by R. Vincent and K. Freudenberger, completed December 18, 1964.

