

SURVEY NO. 2739

SURVEY NARRATIVE TO COMPLY WITH ORS 209.250, REVISED BY CHAPTER 555, O. L. 1963

FOR - ELK LUMBER COMPANY
P. O. BOX 606, MEDFORD, OREGON

PURPOSE - To remonument and perpetuate the quarter section corner common to sections 8 and 9, Township 32 South, Range 2 East, Willamette Meridian.

PROCEDURE -

Found the reference pipe set by Lovejoy prior to construction of logging road to section 9, T. 32 S, R. 2 E, (Recorded Survey no. 843 - Jackson County, Oregon, 1955)

At a point 18.50 feet South of said reference pipe set a 1 inch by 36 inch galvanized steel pipe driven 24 inches in the ground for quarter corner monument.

From said quarter corner monument, a 19 inch Douglas fir bears North 27° East 63.3 feet and a 13 inch Madrone bears South 49° West 15.0 feet.

Both trees are double blazed and scribed "RS 583" in the upper blaze and "BT" in the lower.

Distances were measured to face of blaze and compass variation was set at 20°00' East.

Field work by R. Vincent and K. Freudenberger, December 17, 1964.

