

2814

RESTORED CORNER FOR STATE OF OREGON-DEPARTMENT OF FORESTRY

One quarter corner common to Sections 3 and 4, T33S,
R1E, W.M., Jackson County, Oregon.

ORIGINAL

Stone 18 x 10 x 10 (now missing) from which a:

22" White Oak bears N40E 43 lks.; now 24", exposed portion of
cast of scribes $\frac{1}{4}$.

7" White Oak bears N84W 25 lks.; now missing, clump of 2 oaks
in place.

Original line blazes N and S.

Ravine, course West, 8.70 chains South; in place.

RESTORED

Set 24" x 10" x 10" stone, marked $\frac{1}{4}$ on West and X on top, 12 inches
in ground, and from which a:

14" Ponderosa Pine bears N64W 83.5 ft.; scribed $\frac{1}{4}$ S 4 BT RS359.

10' x 15' x 8' high bears N28 $\frac{1}{2}$ E 66.3 ft.; scribed X.

(Rock outcrop in glade.)

Set 4 x 4 x 72" white painted Cedar post 2.0 ft. SW of corner stone.
Oregon State Forestry Department metal location poster on 6" White
Oak S14E 7.0 ft.

Dated January 21, 1965

Restored by

Present and witnessed by Marvin Pounds



Arnold G. Gibson

