



BEARINGS FROM REC. SURVEY N21260

REGISTERED
OREGON
 LAND SURVEYOR
C. Lind McBeth
 JANUARY 12, 1962
 C. LIND MCBETH
 565

SURVEY FOR BLAIR CROSBY
 IN THE CITY OF MEDFORD
 JACKSON COUNTY, OREGON

BY C. LIND MCBETH L. S.
 JACKSONVILLE, ORE.
 AUGUST 6, 1965

SCALE 1"=100'
 ○=FD 3/4" PIPE
 ●=SET 5/8" PIN

Survey No. 2924

Survey Narrative to comply with O.R.S. 209-250

Survey For: Mr. Blair Crosby
1111 Ross Lane
Medford, Oregon

Purpose of Survey: To set corners for property at the Southeast corner of Jackson & Western.

Survey Location: West Medford Addition, City of Medford.

Basis of Bearing: Survey # 1260

Date: August 10, 1965

Survey Procedure: Found 3/4" Iron Pipes as shown along the West line of Western Avenue and said pipes are referred to in field books # 214 and #420 City of Medford records. I then set up the centerline of Western Avenue from these pipes; and produced this line to intersect the centerline of Jackson, said centerline was determined by concrete monuments at McAndrews and Columbus. Having then control for this survey I set 5/8" x 24" Iron pins on the four corners of this parcel according to the description thereof.



C. Lind McBeth

