



Survey No. 2943

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Carl Peterson, Rt. 1, Box 44, Rogue River, Oregon.

LOCATION: S.W.  $\frac{1}{4}$  OF THE S.W.  $\frac{1}{4}$  of Section 9, Township 35 South,  
Range 4 West, W.M., Jackson County, Oregon.

PURPOSE: To monument the boundaries of tracts shown on map.

PROCEDURE: For control I used the reestablished monuments  
shown on map, the S.W. corner, the West  $\frac{1}{4}$  corner  
and the South  $\frac{1}{4}$  corner of the Section. From these  
controls I marked the boundaries of the tracts shown.

DATUM: Solar. Solar taken on the West line of the Section on  
true line between the S.W. corner and the west  
A corner.

Inst. set on West line, direction to S.W. corner.

Adjusted vertical angle =  $26^{\circ}39'18''$

Adjusted Horiz. angle, left from line to sun  
 $36^{\circ}49'30''$

Date of Solar: 9:45 A.M., October 27, 1965 P.S.T.

Computed bearing of Sun = S.  $36^{\circ}59'$  E.

