

Survey Narrative To Comply With Paragraph 209.250
Oregon Revised Statutes

SURVEY FOR: L.M. Fifield
Talent, Oregon

LOCATION: Tract situated in the Northeast One Quarter (1/4)
of Section 27, Township 38 South, Range 1 West,
Willamette Meridian, Jackson County, Oregon.

PURPOSE: To monument the corners of the tract described
in Volume 224, page 202, Jackson County Deed Re-
cords, also to divide the above parcel into four
tracts as shown on the attached map.

PROCEDURE: The Northeast Corner of Donation Land Claim No. 66
was found as described in the re-established corner
records, but there was no record of the Northwest Corner of Donation
Land Claim No. 63 which was required to establish the West line of
the tract. The boundaries of Donation Land Claim No. 63 was tra-
versed with ties made to all points of record that could assist
the positioning of the corners. By the use of the information,
the Northwest Corner was positioned at a pointed rock boulder
found buried at the position shown on the attached map.

For many years a 2 inch iron pipe has been the re-
cognized Northeast Corner of the Donation Land Claim No. 63. This
positioning of this pipe agreed within reasonable limits with the
record distances and old deed record ties, for this reason the
present position of the corner was accepted.

The above two corners were referenced as shown
in the inset on the attached map.

Basis of bearings--Solar Observations taken on the
traverse line on July 24, 1965. Time - 9:46':00" a.m., Standard
Time. Latitude - 42° 13.95'. Measured altitude - 51° 05.41'.
Eight (8) observations.

April 5, 1966

J.A. Hoffbuhr
Registered Land Surveyor

