

CHARLES H. HURST, L. S.
REGISTERED PROFESSIONAL LAND SURVEYOR
CONSULTING FORESTER
765 SUNRISE AVENUE
MEDFORD, OREGON 97501

3259

County Surveyor
Jackson County Courthouse
Medford, Oregon

October 18, 1966

Dear Sir:

During the course of some staff compass work in the Antelope Creek drainage, the following corners were found and rehabilitated in Section 27, Township 37 South, Range 1 East of the Willamette Meridian:

1/4 corner common to Sections 26 and 27

Found Ponderosa pine stump with butt scribing intact from which evidence I set a brass capped 3/4" x 30" iron pin for corner S 12° W 21.78 feet distant. A Ponderosa pine root crown bears S 77° W 93.72 feet in accordance with the official record. I scribed an 8 1/2" White oak " 1/4S26 483BT " which bears N 11 1/2° E 40.52 feet distant; an 8.2" White oak " 1/4S27 483BT " which bears N 46 1/4° W 42.31 feet distant.

1/4 corner common to Sections 27 and 34



Found Ponderosa pine stump with butt scribing intact from which evidence I set a brass capped 3/4" x 30" iron pin for corner S 78° E 56.10 feet distant. No evidence of the Black oak bearing S 89° E 13.20 feet distant was found. I scribed a 20" Ponderosa pine " 1/4S 27 483BT " which bears N 17° E 35.91 feet distant; a 22" Ponderosa pine " 1/4S27 483BT " which bears N 81° E 56.64 feet distant, there being no suitable trees adjacent to corner in Section 34 to scribe.

Witnessed by Robert W. Malotte, chainman.

Sincerely,

Charles H. Hurst

cc: George G. Moore
604 Whitman Place
Medford, Oregon



Charles H. Hurst

