

Survey Narrative to Comply with Paragraph 209-250  
Oregon Revised Statutes

Survey For: John H. Hill  
1830 Roberts Road., Medford, Oregon  
Richard C. Logg  
195 South 5th St., Jacksonville, Oregon  
M. M. Rogers 6037 Harding Ave.,  
and A.J. Fitzgerald South Gate, California  
Harry A. Lyter  
3101 Capitol Ave., Medford, Oregon

Basis of Bearings: Polaris Observation checking closely to  
McGinty No. 1673

Purpose of Survey:

To establish boundaries of fractional portions of  
unsurveyed tracts of Government land known as Kanaka Flats  
in the Southwest Quarter of Section 31, in Township 37 South  
Range 2 West W.M. by proportionate measurement.

Survey Procedure:

Re-established brass capped pipe monuments were  
found for Southwest corner of Section 31 and South  
1/4 Corner of Section 31, and a 1 1/2" diameter pipe  
monument on The West line of Section 31 cor-  
responding to notes of County Record. A 1" diameter  
steel axle used for surveys of record for center of  
Section 31, and South West corner of Jacksonville  
was found and used on traverse of this quarter sec-  
tion.

Boundary of the Quarter Section was run by traverse  
and the subdivision of the Tracts were computed and  
corners set by distances proportioned according to  
the proportionment of distances of record in original  
Government field notes for The North and South bound-  
aries of Section 31.

The proportionment of the East-West center line of the  
Section was derived from mean proportionment of the  
North line and South line of the West Half of Section 31.



