

Butte Falls, Oregon
December 7, 1966

County Surveyor
Jackson County Courthouse
Medford, Oregon

Dear Sir,

Please record following survey in Public Land surveys.

SECTION 26, T. 33S, R. 2 E., Willamette Meridian.

OBJECT: to subdivide section for designating Medford Corporation lands.

NARRATIVE: Ran transit and chain traverse around exterior section lines and found following original evidence;

SW corner	Brass Cap and BTs
$\frac{1}{4}$ "	27/26 stone, BTs gone, blazes
NW "	Brass Cap and BTs
$\frac{1}{4}$ "	$\frac{23}{26}$ " " " "
NE "	" " " "
$\frac{1}{4}$ "	26/25 " " " "
SE "	" " " "
$\frac{1}{4}$ "	$\frac{26}{35}$ " " " "

Bearings by Solar observations.

West Line: Bearing Due North.

0.0	feet	SW corner			
1321.5	"	set S 1/16 corner	27/26	5/8"x3' rebar, Al. cap	
		scribed RS 461			RS 461
		S 1/16	8" W.Fir	N20°W 8.5'	S 1/16
		S 27 BT			27/26
		" "	8" Maple	S 1°E 11.6'	
		S26 BT			
2643.0	"	$\frac{1}{4}$ corner stone, set 5/8" rebar, Al. cap			RS 461
		scribed RS 461 BT			27/26
		10" W.Fir	S27°E	22.6'	1/4
		40" D.Fir	N76°W	35.6'	
5270.0	"	NW corner			
<u>North Line:</u>		Bearing S89°45'30"E			
0.0	"	NW corner			
2605.4	"	$\frac{1}{4}$ "	$\frac{23}{26}$		
		Bearing N89°50'30"E			
0.0	"	$\frac{1}{4}$ corner			
2671.2	"	NE "			
<u>East Line:</u>		Bearing S0°19'W			
0.0	"	NE corner			
1325.4	"	Set N 1/16 26/25	5/8"x3' rebar	Al. cap	RS 461
		scribed RS 461 BT			N 1/16
		10" W. Fir	N34 E	6.5'	26/25
		10" D. Fir	Due West	12.0'	
2650.7	"	$\frac{1}{4}$ corner 26/25			
		Bearing S0°17'W			
0.0	"	$\frac{1}{4}$ corner			
2645.4	"	SE "			
<u>South Line:</u>		Bearing N89°47'W			
0.0	"	SE corner			
2629.9	"	$\frac{1}{4}$ "	$\frac{26}{23}$		
		Bearing N89°34'30"W			
0.0	"	$\frac{1}{4}$ corner			
2618.1	"	SW "			

(2)

Section 26, T33S, R2E, W.M.

Began at S 1/16 27/26 ran S89°38'30"E 2614.9 feet; set SC 1/16, corner
scribed RS 461 5/8"x3' rebar Al. cap
CS 1/16 RS 461
S 26 BT CS 1/16
26" W.Fir N13°W 19.4' 26
20" " S 8°E 31.0'
thence ran S0°08'30"E 1324.6 feet to 1/4 corner 26
35

Began at N1/16 26/25 ran N89°56'W 2660.5 feet to CN 1/16 corner set
scribed RS 461 BT 5/8"x3' rebar Al. cap
16" Cedar N70°W 44.4' RS 461
36" D.Fir S0°E 8.9' CN 1/16
26

thence ran S 0°08'30"E 1314.8' to CC 1/4 corner, set
scribed RS 461 BT CC 1/4 5/8"x3' rebar Al. cap
26 RS 461
8" W.Fir N6°W 8.8' CC 1/4
7" Maple S24°E 21.0' 26
6" W.Fir N74°E 41.4'
thence ran S89°42'30"E 2649.9 feet to 1/4 corner 26/25.

