



MAP OF SURVEY  
LOCATED IN  
S.E. 1/4 OF SECTION 24, T. 36 S., R. 4 W., W.M.  
JACKSON COUNTY OREGON  
FOR  
**LEO FOSBURGH**

REGISTERED  
**OREGON**  
LAND SURVEYOR  
*J. A. Hoffbuhr*  
NOVEMBER 7, 1947  
**J. A. HOFFBUHR**  
222

J. A. HOFFBUHR, REG. L.S., MEDFORD, OREGON  
SCALE: 1"=100' FEBRUARY 20, 1967  
BASIS OF BEARING-SOLAR OBS. HAYMOR PARK SUB.  
o = SET 5/8" X 24" STEEL REINF. PIN

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
OREGON REVISED STATUES

SURVEY FOR: Leo Fosburgh  
Box 204  
Highway 99 North  
Gold Hill, Oregon

LOCATION: Tract situated in the Southeast One Quarter (1/4)  
of Section 24, Township 36 South, Range 4 West,  
Willamette Meridian, Jackson County, Oregon.

PURPOSE: The description of the tract as described in  
Jackson County Deed Records Volume 569 Page 436  
being incomplete and indefinite in regards to  
dimensions, it was necessary to monument and  
describe the tract originally intended.

PROCEDURE: The Section Corner common to Sections 23, 24, 25,  
and 26 was found as re-established and a traverse was run to the  
tract and the West line was established along the line as presently  
occupied, the East line of HAVMOR PARK SUBDIVISION was extended  
Northerly to establish the East line of the tract and the client  
was advised that it would be necessary to clear title to these two  
boundary lines, the Oregon State Highway control was used for the  
Southerly line and the mean high water line was used for the  
Northerly line. Basis of bearings - Solar observation - HAVMOR  
PARK SUBDIVISION.

March 17, 1967

J. A. Hoffbuhr  
Registered Land Surveyor

