

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250,
REVISED BY CHAPTER 555, O.L. 1963

FOR: BOISE CASCADE CORPORATION
P. O. BOX 100, MEDFORD, OREGON

PURPOSE - To rehabilitate and perpetuate the section corner common to Sections 12 and 13, Township 34 South, Range 1 West, and Sections 7 and 18, Township 34 South, Range 1 East, Willamette Meridian.

PROCEDURE - Found the original Northeast BT which is now a 25.5 inch Ponderosa Pine with upper face open and charred, showing faint scribing; and the original Southwest BT which is now a 21 inch White Oak with open face and all traces of scribing obliterated by decay. Also found the remains of the original Southeast BT which is a charred pine stub with the lower blaze opened and scribing intact. The rock outcrop used as bearing object is present with no definite point marked thereon for reference. This object was used for a distance reference only as I found it too large and too close to the corner point to have a significant influence on bearing in the absence of a definite reference mark.

Set the corner point at the mean of the separate locations from identified original BT's and monumented with a 1 inch by 36 inch galvanized steel pipe driven 10 inches in the ground to bedrock and surrounded with a mound of stone 36 inches in diameter and 20 inches high. This one inch pipe is capped with a 1 1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals:

1967
T34S
 $\frac{12 \parallel 7}{13 \parallel 18}$
WM
RS 583

From the above described monument the original Northeast BT bears North 52° East 188.8 feet; the original Southeast BT bears South 10° East 93.1 feet and the original Southwest BT bears South 16° West 119.8 feet.

NEW REFERENCES - From the above described pipe monument a 7.5 inch White Oak bears South $29^{\circ}30'$ West 96.8 feet. This tree is double blazed and scribed T34S R1W S13 RS583 in upper blaze and BT in lower. Chiseled "+" on top of imbedded boulder bears South $66^{\circ}30'$ East 2.8 feet and chiseled "+" on face of rock outcrop bears North $30^{\circ}00'$ West 18.2 feet. The distance to new bearing tree was measured to face of blaze and compass variation was set at $20^{\circ}00'$ East.

Field work was completed on June 21, 1967, by R. Vincent and J. Gartman.

