

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250
REVISED BY CHAPTER 555, O.L. 1963

FOR: G.L. Brant
Rt. 2, Box 601
Central Point, Oregon

PURPOSE: Reestablish 1/4 corner common to Sections 25 and 36, Township 35 South,
Range 2 West, Willamette Meridian.

PROCEDURE: Found the original Northeast bearing tree, described as an 8" White Oak,
bearing N 50° E, 56 links. Said tree presently measures 13", and a
small piece of reverse scribe was found in the now hollow interior of
said tree. A meridian was brought to corner location from recent
bearings of record for the South line of said Section 36, where the
South 1/4 corner, and the Southeast corner were found as reestablished.
At the corner location I placed a 1" iron pipe with a brass cap
stamped T.35S.,R.2W.

$\frac{25}{36}$
1/4 Cor.
1967

...from which the following bears:
6" W. Oak, S 34°21' W, 9.16 feet, scribed 505 BT
13" W. Oak, N 50° E, 36.96 feet, (Original)
Measurements taken from faces of trees.
June 16, 1967

