



SURVEY FOR: LAWRENCE H. HALLMAN,
1500 E. DANA PLACE, ORANGE, CALIF.
DUANE A. ANDREWS, P.O. BOX 991,
BELLVUE, WASHINGTON.

LOCATION: N 1/2 NW 1/4 SEC. 10, T. 39S, R. 3E W.M.

- = 1/2" + 24" IRON RODS SET UNLESS SHOWN OTHERWISE
- * = 5/8" + 30" IRON RODS SET
- = MON. FOUND

BEARING DATUM: RECORD ROAD E (COUNTY ROAD)
DATE: 8-18-67 **SCALE:** 1" = 200'

JACKSON COUNTY
RECEIVED
SEP 21 1967
SURVEYOR

REGISTERED
OREGON
LAND SURVEYOR

MARCH 10, 1944
L. E. AGER
21

10 11
1/4 COR. FOUND
IRON PIPE & 1 LODGEPOLE PINE BT.

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
 OREGON REVISED STATUTES

SURVEY FOR: Lawrence H. Hallman Duane A. Andrews
 1500 E. Dana Place & P.O. Box 991
 Orange, California. Bellvue, Washington

LOCATION: N $\frac{1}{2}$ NW $\frac{1}{4}$ Section 10, T.39 S., R. 3 E., W.M.

PURPOSE: To monument the corners of a tract of land according to boundary description furnished and subdivide same into 9 parcels.

PROCEEDURE: For N. $\frac{1}{4}$ corner I set a 5/8" + 30" rebar. Found stump of original B.T. in SW Quad.

For Section corner, 3, 4, 9 & 10 found hub with tack at position of corner which checked original field notes. I replaced this with a 3/4" + 26" rebar. Original bearing trees found.

For W. $\frac{1}{4}$ corner I set a 3/4"+ 24" rebar. Found 24" Fir stump (scribe visible) in SW quadrant. Found 22" Dead standing fir stump (scribe visible) in SE quadrant.

East $\frac{1}{4}$ corner: Found iron pipe in place according to reestab. notes.

N 1/16 corner on West line: Set 3/4"+ 24" rebar on true line and midway between the W. $\frac{1}{4}$ corner and NW corner.

References: Measurements to heads of nails in blazes and bearings to same of the following trees:

Nail in blaze on 16" W.F.	bears	N.6 ⁰ 30'	W.,	21.30'
" "	"	" 14" "	"	S.67 ⁰ 20' W. 12.37'
" "	"	" 14" "	"	S.53 ⁰ 35' E. 10.16'

Using the above described corners for control I surveyed and monumented the corners of the tracts as shown on map.

Bearing control: Identical to County Road centerline record.

