



SCALE: 1" = 100'

SURVEY FOR: ORDER OF BELL REAL ESTATE &
EUGENE W. SEITZ, ASHLAND, OREGON.

LOCATION: PORTIONS OF LOTS 4, 5, 12, 13 & 14, SECTION 'E'
OF ROGUE RIVER VALLEY ORCHARDS CO'S. 10
ACRE ORCHARD TRACTS, IN S 1/2 OF SEC. 30,
T. 38 S., R. 1 E., W. M.

- = 1/2" + 30" IRON RODS SET FLUSH
- = MONUMENTS FOUND AS DESC.

DATE: 7-25-66

BEARINGS: SOLAR

JACKSON COUNTY
RECEIVED
JAN 16 1968
SURVEYOR

REGISTERED
OREGON
LAND SURVEYOR

L. E. Ager
MARCH 10, 1944
L. E. AGER
21

3627

3627

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250

OREGON REVISED STATUTES

SURVEY FOR: Order of Bell Real Estate & Eugene W. Seitz,
Ashland, Oregon.

LOCATION: Portions of Lots 4, 5, 12, 13 & 14, SECTION "E" of
ROGUE RIVER VALLEY ORCHARDS COMPANY'S 10 Acre Orchard
Tracts in S $\frac{1}{2}$ of Section 30, T. 38 S., R. 1 E., W.M.

PURPOSE: To monument the corners of tracts as shown on map.

PROCEEDURE: Survey made from monuments shown as found on map.
Butler Lane control from monuments found at property
corners along Lane East of Valley View Road.

BEARING CONTROL: Solar taken on Butler Road Wednesday July 6,
1966 at 9:00 A.M. P.S.T.

Sun app. decl. $22^{\circ}41.5'$ Adj. Vert. angle
 $45^{\circ}23'30''$. Lat. $42^{\circ}14'$
Comp. bearing of Sun= S. $79^{\circ}43'35''$ E.

