



REGISTERED
OREGON
 LAND SURVEYOR

L. E. Ager

MARCH 10, 1944
 L. E. AGER
 21

JACKSON COUNTY
 RECEIVED
 MAR 13 1968
 SURVEYOR

SURVEY FOR: E.E. RASMUSSEN
 RT. 3, BOX 224
 PHOENIX, ORE.

LOCATION: SEC. 2, 3 & 11, T. 38S., R. 1W., W.M.

●● = INDICATE MON. FOUND
 ○ = INDICATE 3/4" IRON PIPES SET FLUSH TO 2" EXP.
 ⊕ = 5/8" + 24" IRON RODS SET FLUSH TO 2" EXP.

DATE: 2-22-68

BEARING BASIS: RECORDED SURVEY #1794

099E - 3660

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250
OREGON REVISED STATUTES

SURVEY FOR: E. E. Rasmussen, Rt. 3, Box 224, Phoenix, Oregon.

LOCATION: Sections 2,3 and 11, T.38 S., R. 1 W., W.M.

PURPOSE: To monument the corners of tracts shown on map of survey.

PROCEDURE: Found stone with + on top for Section corner, the position of which checked good from a property line fence to East from Deed Record description indicating it was used for corner control for prior surveys. Found a 3/4" iron pipe to the East at the intersection of the East-West fence with the North end of a North-South fence line. Made a search for the 1/4 corner common to Sections 2 & 11 but found no indication of corner or bearing trees. I used the monuments as found for control.

Bearing basis: Same as recorded survey No. 1794

