

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
OREGON REVISED STATUTES

SURVEY FOR: Leo L. Davis  
P.O.Box 395  
Klamath Falls, Oregon

LOCATION: Tract situated in the Northeast One Quarter ( $\frac{1}{4}$ )  
and a portion of the Southeast One Quarter ( $\frac{1}{4}$ )  
of Section 28, Township 35 South, Range 2 West,  
Willamette Meridian, Jackson County, Oregon.

PURPOSE: To survey and monument various parcels of land  
in the East One Half ( $\frac{1}{2}$ ) of Section 28 T35S  
R2W W.M as indicated on the attached map.

PROCEDURE: All the corners of the East One Half of Section 28  
were existing, having been established by prior surveys as shown  
on recorded Survey No. 3314 with the exception of the Northeast  
Corner of Section 28 T.35S.R.2W. W.M. The Northeast corner of  
Section 28 was established from an old pine stump, which is the  
remains of the original bearing tree, which is described as a  
36" yellow pine, bearing S69 $\frac{1}{2}$ ° W 283 Links (186.78 feet) in the  
U. S. Government Survey Notes.

The Center Line Perry Road was determined by  
recovered angle-point spikes set by the Office of the County  
Engineer. Curves were designed from topography and monumented  
accordingly.

April 1, 1968

Bernard H. Hendrix  
Registered Land Surveyor

