

Survey Narrative To Comply With Paragraph 209.250
Oregon Revised Statutes

SURVEY FOR: Jerome Fitzgerald
Holcomb Springs Road
Gold Hill, Oregon

LOCATION: Tract situated in Section 26 & the West Half
(1/2) of Section 25, Township 35 South, Range
3 West, Willamette Meridian, Jackson County,
Oregon.

PURPOSE: To monument the corners of the tracts shown
on the attached map.

PROCEDURE: The section corners were located and found as
shown. The Southeast Corner of the Section had been destroyed
in recent years and no evidence of the original corner could be
located. Mr. Jerome Fitzgerald has been familiar with the location
of this corner for many years as this was the family ranch on
which he was raised from a boy.

Affidavits were obtained from Mr. Fitzgerald and Mr. Charles
Hilkey, the owner of an adjacent tract, for he also was familiar
with the original corner location of the section corner.


The use of testaments from these gentlemen, that were familiar
with the original quartz stone, was deemed the most accurate method
of restoring the corners in its original position.

The corner was re-established as shown on the attached map.
The section was subdivided and corners were established as shown
on the attached map.

In the absence of other control for Holcomb Springs Road the
center of the traveled portion was used for centerline and the
right of way line was established 30.00 feet on both sides.

Basis of bearings--Solar Observation.

April 29, 1968



J. A. Hoffbuhr
Registered Land Surveyor

