

SURVEY NO. _____

3766

SURVEY NARRATIVE to comply with paragraph 209.250, Oregon Revised Statutes.

SURVEY FOR: Charles Jackson F. Ward McGulley
Route 1, Box 67L P.O. Box 387
Rogue River, Oregon Rogue River, Oregon

PURPOSE: To survey and monument the S. E. $\frac{1}{4}$, S. E. $\frac{1}{4}$, Section 5, Township 35 South, Range 4 West, Willamette Meridian, Jackson County, Oregon, as shown on the plat.

PROCEDURE: The east-west center line of Section 5 was established by running west from the $\frac{1}{4}$ corner common to sections 5 & 4 to a point from which the $\frac{1}{4}$ corner common to sections 6 & 5 was visible. The line was then established by "balancing in" and proceeding west on a true line to the intersection with the north-south center line of said section. The survey was made with a 300 ft. steel tape and a 1 minute transit.

Re-establishment of $\frac{1}{4}$ corner common to Sections 6 & 5

Set $\frac{3}{4}$ " iron pipe from which the original Bearing Trees;

18" B.O. with healed over blaze bears S 14° W (S 18° W record) 55.4'

20" Fir stump with "B.T." scribe visible bears N 45° E (N 36° E record) 29.0'

New B.T.; 8" laurel bears N 47° E, 50.2'

