

from which a 4" White Oak, which bears N67 1/2°E 133.3 feet, is double blazed and scribed W 1/16 S.1 RS 787 in the upper blaze and BT in the lower blaze. Also a 3 1/2" White Oak which bears S40°E 27.8 feet is double blazed and scribed W 1/16 S 12 RS 787 in the upper blaze and BT in the lower blaze.

5. For the South 1/16 corner common to Section 1 and Section 2, set a pipe stamped as shown below 2 inches in the ground to Lava Rock and surrounded with a mound of stone 3' x 3' x 30" high,

S 1/16
S2 | S1
1968
RS 787

from which a 6 1/2" Incense Cedar, which bears N35°W 23.75 feet, is double blazed and scribed S 1/16 S 2 RS 787 in the upper blaze and BT in the lower blaze. Also a 8" Incense Cedar which bears S44 1/2°E 71.9 feet is double blazed and scribed S 1/16 S 1 RS 787 in the upper blaze and BT in the lower blaze.

6. For the Southwest 1/16 corner of Section 1, set a pipe 24" in the ground and stamped as shown below,

SW 1/16 S1
1968
RS 787

from which a 6 1/2" White fir bears N77°E 9.6 feet. Also a 16" Douglas fir bears S12°W 36.8 feet. Both trees are double blazed and scribed SW 1/16 S1 RS 787 in the upper blaze and BT in the lower blaze.

7. For the Northwest corner of the property described in Deed Records Vol. 598 Page 319 - 320 parcel 1, set a pipe 16 inches in the ground and stamped as shown below.

RS 787
PROPERTY
CORNER
1968

8. For the Southwest corner of the property described in Deed Records Vol. 598 Page 319 - 320 parcel 1, set a pipe stamped as shown below 14" in the ground to lava rock and surrounded by a mound of stone 2 1/2' x 2' x 1 1/2' high.

RS 787
PROPERTY
CORNER
1968

The distance to all new bearing trees was measured to the face of the blaze and the compass variation was set at 20° East. The field work was completed August 29, 1968, by B. L. Brandt, Max Stockford, James Popham, and Earl VanHoy.

REGISTERED
OREGON
LAND SURVEYOR
Brice L. Brandt
JULY 10, 1967
BRICE L. BRANDT
787

JACKSON COUNTY
RECORDED
SEP 30 1968
SURVEYOR

CORNERS SET: Set corner pipes as indicated on the Survey Map.

1. For the center of the Section set a pipe 36" in the ground stamped as shown below.

C 1/4 S 1
1968
RS 787

As there were no trees within 200 feet, no bearing trees were scribed.

2. For the Center West one-sixteenth corner, set a pipe 27 inches in the ground and stamped as shown below,

C $\frac{W 1/16}{S 1}$ C
1968
RS 787

from which a 6" White Oak bears S33 1/2° W 4.3 feet. Also a 7" White Oak bears N11 1/2° W 25.9 feet. Both trees are double blazed and scribed CW 1/16 S.1 RS 787 in the upper blaze and BT in the lower blaze.

3. For the Center South one-sixteenth corner. Set a pipe 0 inches in the ground on lava rock and surrounded by a mound of stone 3' x 3' x 2 1/2' high and stamped as shown below,

C
S 1/16 S 1
C
1968
RS 787

from which a 5 1/2" White Oak bears N73 1/2° E 18.0 feet. Also a 7" White Oak bears N85° W 31.8 feet. Both trees are double blazed and scribed CS 1/16 S.1 RS 787 in the upper blaze and BT in the lower blaze.

4. For the West 1/16 corner common to Section 1 and Section 12 set a pipe 1" in the ground and surrounded by a mound of stone 3' x 3' x 30" high and stamped as shown below,

W 1/16 $\frac{S 1}{S 12}$
1968
RS 787

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250,
REVISED BY CHAPTER 555, O. L. 1963

FOR: BOISE CASCADE CORPORATION
P O. Box 100, Medford, Oregon

PURPOSE: To subdivide the southwest one-quarter of Section 1, Township 33 South, Range 2 East, Willamette Meridian and to determine the property lines of that property described in the Deed Records of Jackson County Volume 598 Page 319 - 320.

PROCEDURE: Ran a transit traverse along the one-quarter section lines and closed around the Southwest one-quarter of Section 1. Set the one-sixteenth corners to the Southwest one-quarter section and traversed the one-sixteenth lines setting the Southwest one-sixteenth corner at the intersection thereof. Set the Northwest property corner and the Southwest property corner as called for in the deed and traversed the line between them.

CORNERS FOUND:

1/4 Corner $\frac{36}{1}$ - Found the 1" galvanized iron pipe with 1 1/2" expander filled with pot metal and marked "T.32 & 33 S $\frac{36}{1}$ 1/4 cor. 1952 C.S." 7 inches above the ground as called for in the 1952 County Surveyor Re-establishment.

1/4 Corner $\frac{1}{12}$ - Found the 1" galvanized iron pipe 1 inch above the ground as called for in the 1940 County Surveyor Re-establishment. Also found one original B.T. and the C.S. B.T. with scribe visible on both.

SECTION CORNER $\frac{2}{11} \frac{1}{12}$ - Found the 2" iron pipe 3 inches below the ground as called for in the 1929 County Surveyor Re-establishment. Also found the 12" Black Oak bearing tree scribed in 1929 and the Douglas fir bearing tree and the Incense Cedar bearing tree as called for in the 1957 re-establishment by the County Surveyor.

1/4 Corner 2|1 - Found the original NW bearing tree now a 20" live, standing Ponderosa pine with scribing visible and the original NE bearing tree now a 24" Ponderosa pine stump with scribing visible. Also found a 1" galvanized iron pipe with 1 1/2" expander filled with pot metal and marked "T33S, R2E 2|1 1/4 cor." 10" above the ground 1.7 feet from its proper location. I moved the pipe to the proper location for the corner from which the original NW Ponderosa pine bearing tree bears N58°W 19.8 feet and the original NE Ponderosa pine stump bears N7 1/2°E 52.8 feet. To the pipe I added the marks "RS 787" and scribed an 18" Douglas fir which bears S84°E 32.2 feet from the corner.

1/4 Corner 1|6 - Found the 1" galvanized iron pipe flush with the surface of an existing road as called for in the re-establishment by the County Surveyor in 1953. As the top of the pipe has been bent over I used the center of the pipe below the bend as the point for the corner. Also found the two County Surveyor bearing trees scribed in 1953 with the faces closed.