

Survey Narrative to Comply with Paragraph 209.250
Oregon Revised Statutes

Mark E. Boyden
Jackson County Surveyor
Medford, Oregon

In re: The rehabilitation of the one-quarter section corner, common to sections 21 and 28, Township 38 South, Range 3 West of the Willamette Base and Meridian, Jackson County, Oregon.

1/4 Section Corner 21 and 28

Found the 1 inch galvanized iron pipe and the two bearing trees as reported in the County Surveyors re-establishment records and dated April 18, 1935. The above mentioned bearing trees are as follows:

a stump of a 22 inch fir with the BT visible bears S. 12°02'W. a distance of 74.43 feet to the face of blaze. (county record; scribed a 24 inch red fir CS-BT and bears S. 12½°W., 74.5 feet.)

a 21 inch black oak with CS visible in relief bears N. 61°25'W. a distance of 47.93 feet to the face of the upper blaze. (county record; an 18 inch black oak scribed CS-BT bears N. 61½°W., 48.0 feet.)

From said 1/4 section corner, I take two new bearing trees as follows:

scribed a 11 inch diameter Laurel ½ S28 BT which bears S. 09°16'E. a distance of 47.17 feet to the center of said tree.

scribed a 6 inch diameter Fir ¼ S21 BT which bears N. 20°07'E. a distance of 43.45 feet to the center of said tree.

October 31, 1968

Everett L. Swain,
Professional Land Surveyor
Bennett Austin, chairman
Jack Huston, chairman

