

CHARLES H. HURST


REGISTERED LAND SURVEYOR

CONSULTING FORESTER

~~723 BUNNICK AVENUE~~

MEDFORD, OREGON 97501

28 North Oakdale



January 28, 1969

County Surveyor
 Jackson County Courthouse
 Medford, Oregon 97501

Dear Sir:

Reference is made to the southwest corner of Donation Land Claim No. 44, Township 38 South, Range 1 East of the Willamette Meridian, Jackson County, Oregon.

In correlating certain information in my files with that data shown for Road Record No. 3, pages 9-12 and the description contained in Commissioner's Journal Volume 3, page 128, Report of Survey by R. W. Kennedy, April 29, 1896, I located a 1" iron pipe buried approximately $1\frac{1}{2}$ feet deep in the south-westerly portion of the intersection of Valley View Road West and the Ashland-Climax Road.

This pipe, I believe, may be the gas pipe referred to by Kennedy. If so, then said pipe is an accessory to the southwest corner of D.L.C. 44 which has been lost during the intervening years.

This pipe has been referenced as follows:

Found 1" black iron pipe $1\frac{1}{2}$ feet below blacktop from which I set:

a concrete nail in the northwest corner of bridge abutment which bears S 15° E 48.60 feet, a concrete nail in the southwest corner of a concrete box outlet for culvert which bears S 71° E 51.97 feet, a $\frac{1}{2}$ " iron pipe (1910 road P.I.) bears N 60° E 36.5 feet, plus or minus.

Bearings by hand compass.

This report may be of assistance at some future date should the location of said D.L.C. corner be required.

Yours very truly,



Charles H. Hurst
 CHARLES H. HURST
 Surveyor