

SURVEY NARRATIVE TO COMPLY WITH ORS 209.250
REVISED BY CHAPTER 555, O. L. 1963

FOR: BOISE CASCADE CORPORATION
P.O. BOX 100, MEDFORD, OREGON

PURPOSE: To rehabilitate and perpetuate the section corner common to sections 9, 10, 15 and 16, Township 35 South, Range 2 West, Willamette Meridian.

PROCEDURE: I found the original Southeast BT which is now a 17 inch Douglas fir stump with "BT" scribe identifiable on the down tree. The original Northeast BT is now a 13 inch dying black oak. The original Northwest BT which is now a 9 inch black oak is in good condition with both faces closed. The original Southwest BT is now a 13 inch black oak in good condition with both faces closed. No evidence of the original corner stake could be found.

From the above evidence, we set a one inch by 36 inch galvanized iron pipe capped with a 1 1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals and driven 30 inches in the ground at the mean intersection of the original distances.

T35S R2W
S9 | S10
S16 | S15
1969
RS787

From the above described monument the original Northeast bearing tree bears N77°E, 24.0 feet; the Southeast bearing tree bears S76°E, 16.8 feet; the Southwest bearing tree bears S78 1/2°W, 6.5 feet and the Northwest bearing tree bears N36°W, 4.0 feet.

NEW REFERENCES: I scribed a 6 inch Douglas fir "T35S R2W S10 RS787" in the upper blaze and BT in the lower blaze which bears N56 1/2°E, 21.8 feet from the corner pipe. I also scribed a 10.5 inch black oak "T35S R2W S15 RS787" in the upper blaze and BT in the lower blaze which bears S72°E, 30.5 feet from the corner monument. The distances to the new bearing trees were measured to the center of the tree. The compass variation was set at 20°East.

Field work was completed on March 3, 1969 by B. L. Brandt and J. Gartman.

