

SURVEY NARRATIVE TO COMPLY WITH ORS 209.250,  
REVISED BY CHAPTER 555, O.L. 1963

FOR: BOISE CASCADE CORPORATION  
P.O. BOX 100, MEDFORD, OREGON

PURPOSE: To rehabilitate and perpetuate the one-quarter corner common to sections 9 and 10, Township 35 South, Range 2 West, Willamette Meridian.

PROCEDURE: I found the original Southeast BT, now a 12 inch black oak which A. T. Brown, the deputy county surveyor, reported finding in 1914 when he reestablished the corner. The "B" of the BT scribe was identified. I also found the 12 inch black oak scribed by Brown in 1914 with the faces closed. I set a 1 inch by 36 inch galvanized iron pipe capped with a 1 1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals and driven 30 inches in the ground beside the stone set by A. T. Brown in 1914. The stone is imbedded 14 inches in the ground and has been run over by a tractor destroying the marks made by Brown.

1/4  
S9 | S10  
1969  
RS 787

From the above described monument the original Southeast bearing tree bears S79°E, 57.4 feet and Brown's bearing tree bears S55 1/2°W, 44.6 feet.

NEW REFERENCES: I scribed a 10.5 inch ponderosa pine "1/4 S10 RS 787" in the upper blaze and BT in the lower blaze which bears S52 1/2°E, 33.0 feet from the corner pipe. The distance to the new bearing tree was measured to the center of the tree. The compass variation was set at 20°East.

Field work was completed March 3, 1969 by B. L. Brandt and J. Gartman.

