

SURVEY NARRATIVE TO COMPLY WITH ORS. 290.250
REVISED BY CHAPTER 555, O. L. 1963

FOR: BOISE CASCADE CORPORATION
P.O. Box 100, MEDFORD, OREGON

PURPOSE: To rehabilitate and perpetuate the one-quarter corner common to sections 9 and 16, Township 32 South, Range 2 East, Willamette Meridian.

PROCEDURE: I found the original Northwest BT lying on the ground with the "1/4" scribe visible. The tree has been moved from its original location by logging. John Gartman showed me a well defined stump hole where he had seen the cedar in the fall of 1968 when he opened the face to observe the scribe. As the ground has been disturbed by logging, no evidence of the original corner stone could be found. The original Southwest BT is now well rotted Douglas-fir stub.

From the above evidence, we set a one inch by 36 inch galvanized iron pipe capped with a 1 1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals and driven 8 inches below the ground to protect it from future logging.

1/4 S9
 S16
 1969
 RS787

From the above described monument the stump hole of the original Northwest incense cedar bearing tree bears N13°W 44.8 feet and the original Southwest Douglas-fir bearing tree bears S4 1/2°W 20.5 feet.

NEW REFERENCES: I scribed a 34 inch incense cedar "1/4 S9 RS787" in the upper blaze and "BT" in the lower blaze which bears N44 1/2 W 82.5 feet from the corner pipe. I also scribed a 17 inch Douglas-fir "1/4 S16 RS787" in the upper blaze and "BT" in the lower blaze which bears S60 1/2 E 30.7 feet from the corner pipe. The distances to the new bearing trees were measured to the center of the tree. The compass variation was set at 20° East.

Field work was completed on April 28, 1969 by B. L. Brandt and J. Gartman.

