

SURVEY NO. 4055

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

REVISED BY CHAPTER 555, O.L. 1963

FOR: C.F. Stearns
342 Vista Ave.
Ashland, Oregon

PURPOSE: To reestablish and monument the East line of Lot 7, Block 46 of the SUMMIT ADDITION to the City of Ashland.

PROCEDURE: Recovered the street centerline monuments as shown on the accompanying map. The original monument at Vista and Mead appears to have been destroyed sometime in the past by water line construction and was reestablished in this survey from the city ties as shown in page 82 of the City of Ashland Street Monuments Tie Book. It might also be noted that the city references to the monument at Mead and Pearl Street and Gresham and Vista Street have been destroyed. The Northeast corner of Lot 7 was reestablished on proportional Measurement along Vista Street, which agreed with the 3/4" iron pipe found for said corner. The bearing for the East line of Lot 7 was established by holding parallel to the center of Gresham Street and distance on this Lot line was established according to the proportional measurement indicated along the East line of BLOCK 46 along Gresham Street.



George R. Burrell

