

SURVEY NARRATIVE TO COMPLY WITH ORS, 290.250
REVISED BY CHAPTER 555, O.L. 1963

FOR: BOISE CASCADE CORPORATION
P.O. BOX 100, MEDFORD, OREGON

PURPOSE: To rehabilitate and perpetuate the section corner common to Sections 11, 12, 13 and 14, Township 35 South, Range 1 East, Willamette Meridian.

PROCEDURE: I found the corner stone set by C.F. Rhodes, the County Surveyor in 1918, firmly in place with the four notches on the south side and a large "X" on top. I also found Rhodes' Northwest bearing tree, now a well rotted Douglas fir stub with scribe marks faintly discernable, which bears N44°W 8.4 feet. His Southeast bearing tree, now a down and rotted incense cedar, bears S73°E 22.0 feet more or less from the corner stone.

From the above evidence, I set a 1 inch by 36 inch galvanized iron pipe, 24 inches in the ground and topped with a 1 inch to 1 1/2 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals, beside the corner stone.

T35S R1E
S11 | S12
S14 | S13
1969
RS 787

NEW REFERENCES: I scribed a 6 inch Madrone "S12 T35S R1E RS787" in the upper blaze and "BT" in the lower blaze which bears N68°E 23.0 feet from the corner stone. I also scribed a 11 inch Madrone "S13 T35S R1E RS787" in the upper blaze and "BT" in the lower blaze which bears S34°E 15.3 feet from the corner stone. I further scribed a 9 inch Madrone "S14 T35S R1E RS787" in the upper blaze and "BT" in the lower blaze which bears S55°W 3.8 feet from the corner stone. I also scribed a 10 inch Madrone "S11 T35S R1E RS787" in the upper blaze and "BT" in the lower blaze which bears N25°W 31.5 feet from the corner stone. All distances were measured to the upper face of each bearing tree. The compass variation was set at 20° East.

Field work was completed on July 31, 1969 by B. L. Brandt and R.A. Morris.

