

SURVEY NARRATIVE TO COMPLY WITH ORS. 290.250
REVISED BY CHAPTER 555, O.L. 1963

FOR: BOISE CASCADE CORPORATION
P.O. BOX 100, MEDFORD, OREGON

PURPOSE: To rehabilitate and perpetuate the one-quarter corner common to Sections 11 and 12, Township 35 South, Range 1 East, Willamette Meridian.

PROCEDURE: I found the stone set by C.F. Rhodes, the County Surveyor in 1918, firmly in place with the "1/4" readily identifiable. Rhodes' notes call the "1/4" on the West face, but I found it on the East face. I also found the original Southeast bearing tree, a burned cedar stub with scribing visible, which bears $S61^{\circ}E$ 7.6 feet from Rhodes' corner stone. No evidence of the original Southwest bearing tree or the 9 inch hemlock which Rhodes scribed could be found.

From the above evidence, I set a 1 inch by 36 inch galvanized iron pipe capped with a 1 1/2 inch to 1 inch galvanized bell reducer filled with pot metal and stamped as shown below in 1/8 inch letters and numerals and driven 24 inches in the ground beside the corner stone.

T35S R1E
1/4
S11 | S12
1969
RS 787

NEW REFERENCES: I scribed a 9 inch Douglas fir "1/4 S11 RS787" in the upper blaze and "BT" in the lower blaze which bears $N51^{\circ}30'W$ 11.0 feet from Rhodes' cornerstone. I also scribed a 9 inch Madrone "1/4 S12 RS787" in the upper blaze and "BT" in the lower blaze which bears $N50^{\circ}E$ 14.9 feet from Rhodes' corner stone. The distances to the new trees were measured to the face of the blaze. The compass variation was set at 20° East.

Field work was completed on July 31, 1969 by B. L. Brandt and R.A. Morris.

