



S. 33	S. 34
S. 4	S. 3

SURVEY IN S.E. 1/4 SEC. 33 T. 38 S. R. 1 W., WM.
 FOR
 MRS. EARL WATSON
 61-23-3

BY EDWARD MCGINTY
 MEDFORD, OREGON
 MAY 20, 1969

SCALE 1" = 100'
 • = 1/2" I. PIN
 ○ = 5/8" I. PIN
 ● = 3/4" I. PIN

REGISTERED
 OREGON
 LAND SURVEYOR

Edward A. McGinty
 JULY 10, 1953
 EDWARD A. MCGINTY
 301

JACKSON COUNTY
 RECORDED
 SEP 18 1969
 SURVEYOR

Survey No. 4078

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209-250

Survey for: Mrs. Earl Watson 61--23
1848 Anderson Crk. Rd.
Talent, Oregon 97540

Survey by: Edward A. McGinty, R.S.
Medford, Oregon
May, 1969

Basis of Bearing: Previous Survey No. 1786

Precedence of Survey:

From previous survey determined center line of the County road. This location reviewed by the Assistant Co. Engr., also the location of the center line extending southwesterly was approved. He also stated that the road should be 60 feet instead of 40 feet. (note, a portion of the road is fenced at approx. 40 ft. right of way)

The westerly line shown on this survey is approx. only and not to be construed otherwise (note, Section should be sub-divided, and client is aware of this.) Also, iron pins set near said line are witness corners.

Iron pins set being 5/8 in. x 24 in., approx. flush with the surface and iron pipe set P.J's on the county road being 1/2 in. x 10 in., approx. 1 in. deep.

