


SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250
REVISED BY CHAPTER 555, O.L. 1963

FOR: Ellen C. Hall (Realtor)
343 E. Main
Ashland, Oregon

PURPOSE: To establish the West line of Government Lot No. 1 in Section 31, Township 39 South, Range 2 East of the Willamette Meridian, Jackson County, Oregon.

PROCEDURE: Commenced this survey at the North one quarter ($\frac{1}{4}$) corner of Section 31, which point is a 4 inch by 3 inch sandstone exposed 3 inches with a cross on top. As this corner may be in danger due to construction, I established two new bearing trees as follows:
A 15 inch White Oak bears North 87° 46' West 23.78 feet; a 8 inch White Oak bears South 70° 40' East 21.58 feet. Both trees were scribed L.S. B.T. Distances were taken to the face of the blaze. Bearings were obtained from Recorded Survey No. 3801. From the North one quarter ($\frac{1}{4}$) corner of Section 31 the line was run South 0° 08' 40" West on a direct line of sight to the South one quarter ($\frac{1}{4}$) corner of Section 31 (a B.L.M. brass cap). 1 inch by 1 $\frac{1}{2}$ inch by 20 inch wood stakes were set approximately 100 feet apart in locating the line to a point near the Southwest corner of Gov. Lot No. 1. A 5/8 inch by 24 inch iron pin was set 6 inches deep for a witness to this line South 0° 08' 40" West 393.94 feet from the North one quarter ($\frac{1}{4}$) corner of Section 31. No map is included with this report.

Sept. 9, 1969

*George Burrell*