

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Klamath Plywood Corporation
P. O. Box 1239
Klamath Falls, Oregon 97601

PURPOSE: To remonument a section corner position disturbed by logging operations.

PROCEDURE: At the Section corner common to Sections 13 and 24, Township 38 South, Range 4 East on the range line between Ranges 4 and 5 East, found the 15" x 15" x 20" basalt stone remaining, with portions broken off from a fallen log. Removed said stone and set a 1" x 36" galvanized iron pipe with 2-1/2" bronze cap stamped:

T 38 S
R 4 E 5 E
13 | 18
24 |
R.S. 281

36" in the ground for corner from which:

The original bearing tree (now a 36" Shasta Fir) with scribe marks visible in the unhealed portion of the lower blaze bears North 23-1/2° West, 43.6 feet to the center of the tree (Record = North 23° West, 43.6 feet);

The original bearing tree (now a 39" Shasta Fir) with scribe marks plain on the single lower blaze bears South 81° West, 54.1 feet to the center of the tree (Record = South 84° West, 54.1 feet).

October 31, 1969

Mark E. Boyden

C. S. Glidden

