

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250
 REVISED BY CHAPTER 555, O.L. 1963.

FOR: Hanscom Brothers
 Little Butte Star Route
 Box 275
 Eagle Point, Oregon.

PURPOSE: To survey and monument 16 parcels, as directed by client.

PROCEDURE: A traverse was run, tying in the four One Quarter corners, along with the Southeast and Northeast corners of Section 2. From this survey data, the center of the Section was determined and monumented. The location for Lots 3 and 4 of EAGLE HEIGHTS FRUIT FARM was also determined, and monumented as shown. The south line of these lots lies approximately 30 feet into Relocated Stevens Road. The parcels were then monumented as shown on the accompanying Plat.

Following are descriptions for corners monumented by $\frac{1}{2}$ " pipes with metal discs.

Center One Quarter, disc stamped: T 36 S, R 1 W
 $C\frac{1}{4}$
 S2
 1969

Center-North 1/16 corner, disc stamped: T 36 S, R 1 W
 CN 1/16
 S 2
 1969

North 1/16 corner between Secs. 1 and 2: T 36 S, R 1 W
 S2 + S1
 N 1/16
 1969

Center-East 1/16 corner, disc stamped: T 36 S, R 1 W
 CE 1/16
 S 2
 1969

No witness trees were scribed for these corners.

