

Butte Falls, Oregon
April 8, 1970

County Surveyor
Jackson County Courthouse
Medford, Oregon

Dear Sir:

Please record following in Public Land
Records.

1/4 Corner common to Sections 7, T34S,R2E and
12, T34S,R1E, W. M.

Found Oak BT Sec. 12 at calls; rotted out.
Found Sec. 7 BT to be a Sugar Pine at calls
instead of Oak. Cut out 1/4S and ~~BT~~, scribes.

Set 2" Iron pipe and iron cap;

RS 461
1/4
S12 / S7
R1E T 34S R2E

Scribed- RS 461 1/4S12 BT
9" Cedar N79°W 36.1'

Scribed- RS 461 1/4S17 BT
10" D. Fir S6°E 40.2'

