



MAP OF SURVEY
 LOCATED IN
 HIGHLAND PAEL TRACT, ASHLAND, OREG.
 DONATION LAND CLAIM NO. 33, TWP. 39 S. R. 1 E., W. M.
 JACKSON COUNTY OREGON

FOR
HELEN O. MOFFIT

EVERETT L. SWAIN, R.L.S. ASHLAND, OREGON
 SCALE: 1" = 100'
 BASIS OF BEARING U.S.C. & G.S. TRUE BEARING
 O SET 3/4 INCH GALV. IRON PIPE TAGGED RLS 759
 • FOUND MON. AS NOTED.

JACKSON COUNTY
 RECORDED
 JUL 17 1970
 SURVEYOR

REGISTERED
 OREGON
 LAND CONVEYOR
 Everett L. Swain
 JULY 9, 1968
 EVERETT L. SWAIN
 759

SURVEY NO. 4279

Survey Narrative to Comply with Paragraph 209.250
Oregon Revised Statutes

SURVEY FOR: Helen O. Moffit
475 Auburn Street
Ashland, Oregon

LOCATION: Situated in Highland Park Tract, Ashland, Oregon
in Donation Land Claim 39, Township 39 South, Range
1 East of the Willamette Base and Meridian, Jackson
County, Oregon.

PURPOSE: To monument Lot 36 and the Easterly 35 feet of Lot
35 per Highland Park Tract Subdivision.

PROCEDURE: Commenced this survey in the vicinity of Gresham and
Iowa Streets. The intersection monuments were recovered
per the "City of Ashland" reference notes. From the
control as found and shown on the Accompanying map,
set the corners of the above described tract. A fence
encroachment of 0.9 feet, more or less, occurs along
a portion of the West boundary. The following
equipment was utilized to execute this survey: Model
6A Geodimeter, Wild T-2 Theodolite and a Invar Sub-
tense Bar.

July 10, 1970

Everett L. Swain
Professional Land Surveyor
Ashland, Oregon

