



MAP OF SURVEY  
 LOCATED IN  
 D.L.C. NO. 50, S.E. 1/4 SEC. 29, T. 37 S., R. 1 W., W. M.  
 JACKSON COUNTY OREGON  
 FOR  
 GOLD SEAL GRECIAN SPA  
 J. A. HOFFBUHR, REG. L.S., MEDFORD, OREGON.  
 SCALE: 1" = 100' 9/25/70  
 BASIS OF BEARING - R.S. 2903  
 • SET 5/8" X 24" IRON REINFORCING PIN

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
 OREGON REVISED STATUTES

SURVEY FOR: Gold Seal Grecian SPA  
 P. O. Box 1092  
 Bend, Oregon

ATTENTION: MR. KELLY

LOCATION: Southeast One Quarter (1/4) of Section 29,  
 Township 37 South, Range 1 West, Willamette  
 Meridian, Jackson County, Oregon.

PURPOSE: To monument the Southwest Corner of Jackson  
 County Deed Record, Volume 411, Page 461.

PROCEDURE: The centerline of Crestbrook Road was established  
 by the intersection monument at Barnett Road and Crestbrook Road  
 and the Northeast Corner, Donation Land Claim No. 50. The deed  
 calls for the Southwest Corner of Deed Record 411-461 to also be  
 the Southeast Corner of Deed Record 409-72. This corner was  
 established by Recorded Survey No. 294, but had been destroyed.  
 The same record angles and the same procedure was used to establish  
 the corner as was shown on the Recorded Survey, but two iron pins  
 found did not fit the locations shown.

Basis of bearings--Recorded Survey No. 2903.

October 29, 1970

REGISTERED  
 OREGON  
 LAND SURVEYOR  
*J. A. Hoffbuhr*  
 NOVEMBER 7 1947  
 J. A. HOFFBUHR  
 222

JACKSON COUNTY  
 RECORDED  
 DEC 22 1970  
 SURVEYOR

J. A. Hoffbuhr  
 Registered Land Surveyor