

S 85° 33' 00" W
227.5

P.O.B. from which, the N.E. Cor. of D.L.C. No. 48, T39SR1E
(a 1" iron pipe w/brass cap) bears West 1088.9 feet and
North 1214.8 feet.

REF. R.S. NO. 4339

N 71° 02' 50" W

2060.4



Basis of Bearings: Rec Survey no. 4339

- = Set 1" X 30" Galv. I. Pipe (taged r.l.s. 638)
- = Fd. 1" G.I. Pipe, unless noted otherwise

SCALE 1" = 100'

1005.05
927.0

S 18° 37' 00" W

49.0 ACRES

S 81° 51' 00" E 37.41

Cor. from which, the E.S.E. Cor. of D.L.C.
No. 52, T39SR1E (a 1" iron pipe w/brass cap
set in conc.) bears South 3590.90 feet
and East 50.00 feet.

FD. 5/8" I. PIN

N 34° 48' 30" E 308.24
DEAD INDIAN CO. RD.


existing & projected
SouthWesterly

EAST 779.17

SOUTH LINE D.L.C. NO. 49 AND 50

NORTH 400.00

EAST LINE D.L.C. NO. 52



REGISTERED
OREGON
LAND SURVEYOR

George Burrell

JULY 10, 1964
GEORGE R. BURRELL
638

MAP OF SURVEY

For: Minnie Owen Parker Ashland, Oregon
Located in the E1/2 Sec. 11 & W1/2 Sec. 12 T39S
R1E W.M. Jackson County, Oregon

By: George Burrell Land Surveyor Dec. 29, 1970

REF. R.S. NO. 3488

Approx.

S 40° 40' 00" E Centerline
226.55

S 68° 32' 29" E
98.18

S 88° 17' 23" E
175.90

REF. R.S. NO. 3645

N 82° 15' 09" E
521.62

Creek

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250
REVISED BY CHAPTER 555, O.L. 1963

FOR: Minnie Owen Parker
c/o Briggs & Munsell, Attorneys
115 E. Main Street
Ashland, Oregon

PURPOSE: To monument and describe the tract as shown on the
accompanying map.

PROCEDURE: The record of Recorded Surveys No. 3488, 3645 and
4339 were utilized in calculating the tract bound-
aries. The 1 inch iron pipe set for the property
corner near the Northeast corner of DLC No. 52 was
established 50 feet West and 50 feet North of the
theoretical position for the Northeast corner of
DLC No. 52 as determined from the East Southeast
corner of said claim. A search was made for evi-
dence of the Northeast corner of Claim No. 52 and
the corners between DLC No. 49 and 50 to the East
with negative results. It is possible that the
Southeast corner of Claim No. 50 may be recovered
by further investigation, as a large rotten Oak
stump was found on an East bearing from the theo-
retical position for the Northeast corner of Claim
No. 52. As the distance was not measured and no
evidence of scribing was found, no further invest-
igation was made.

REGISTERED
OREGON
LAND SURVEYOR

George Burrell

JULY 10, 1964
GEORGE R. BURRELL
638

