



SCALE 1" = 100'

Basis of Bearings: Recorded Survey no. 2984

- = Set 5/8" x 24" Iron Pin tagged RLS 638
- ⊙ = Found 1 1/2" galv. Iron pipe
- = Found 5/8" iron pin, unless otherwise noted
- = Lines Not Established by this Survey

REGISTERED
OREGON
LAND SURVEYOR

George R. Burrell

JULY 10, 1964
GEORGE R. BURRELL
638

JACKSON CO.
RECORDED
MAR 5 1971
SURVEY

MAP OF SURVEY

Located in Gov't. lot 10 Section 26, Twp. 36 South, Range 3 W. W.M.
For: R. B. Hage 613 S.E. 160th Portland, Oregon
By: George R. Burrell Land Surveyor Feb 17, 1971

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250
REVISED BY CHAPTER 555, O.L. 1963

FOR: R.B. Hage
613 S.E. 160th
Portland, Oregon

PURPOSE: To partition the tract described in O.R. 68-10142
J.C.,O. as shown on the accompanying map.

PROCEDURE: The South line of D.L.C. No. 38 was established according to Recorded Survey No. 2984. Old Stage Road centerline was established from the county control monuments found on said centerline. The line described in O.R. 68-10623 was established according to record from the Southeast corner of D.L.C. No 38 and the monument found near the Northerly Right of Way of Old Stage Road. The monuments found along the Southerly line of the tract described in O.R. 68-10623 (see Recorded Survey No. 3657), were held as control for direction only, the true corner intersections being as shown on the accompanying map. The remaining boundaries of the parent tract were established according to record. That portion of Government Lot 10 lying North of the South line of D.L.C. No. 38 was not established by this survey.

REGISTERED
OREGON
LAND SURVEYOR

George Burrell

JULY 10, 1964
GEORGE R. BURRELL
638

