

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209-250

Survey for: D. L. Stevenson & Stanley Smith 71-25
 Rt. 4, Box 1440
 Bend, Oregon 97701

Survey by: Edward A. McGinty, R.S.
 Medford, Oregon
 June, 1971

Basis of Bearing: Solar Observation

Location of Survey: N. 1/2 of Sec. 27, T36S, R4W.



Precedence of Survey:

This survey is a partial survey of Mining Claims, Apex No. 1 and Apex Extension, as designated by the clients. No attempt was made to confirm the 1/4 cor. and the W. 1/16 corner between Sec. 27 and 34 shown on Survey No. 2955. No attempt was made to show conflicts or encroachments on other claims or private ownership. This survey was ~~not~~ open ended and the traverse between Pt. A and B was not made for any adjustment.

- Pt. A - Found a 3/4 in. iron pipe, tag. No. 404, being the W. 1/16 Cor. betw. Sec.s 27 & 34 according to Survey No. 2955.
- Pt. B - Found a 1 1/4 in. iron pipe, Tag. No. 404, being the 1/4 cor. betw. Sec.s 27 and 34, according to survey No. 2955.
- Pt. C - Found a 3/4 in. iron pipe, tag No. 404, being on the Sec. line and DLC line, according to survey No. 2955.

At the NE. and NW. and SW. corner of claims set a 5/8 in. re-bar approx. 29 ins. long, and 25 ins. in the ground; also at the NE. cor. of Apex Extension

Near mid point of Apex No. 1 on the North line, set a 5/8 in. x 29 in. re-bar and also at the west end center set a 5/8 in. x 15 in. re-bar.



Edward A. McGinty

