

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
 OREGON REVISED STATUTES

SURVEY FOR: La Verne Miller
 P. O. Box 507
 Jacksonville, Oregon



LOCATION: Tract is composed of Lots 3 & 4 and the adjoining
 One Half (1/2) of 102 Street as shown on the
 Original Map of Jacksonville, Oregon.

PURPOSE: To monument the corners of the perimeter corners
 of a tract composed of Lots 3 & 4, Block 46 of the
 Original Town of Jacksonville, including the
 adjoining Westerly One Half (1/2) of 102 Street.

PROCEDURE: The controls for the centerlines of California,
 Oregon and 101 Streets were located as shown on previous surveys.
 The centerline of California Street was projected Westerly as shown
 of record using the existing centerline control and record distances.
 It was noted that Survey No. 2189 was predicated on lots in Block
 45 being 50.50 feet in width instead of 50.00 feet. The surveyor
 was notified and it was agreed that the centerline monuments set
 on 102 Street should be 4.00 feet easterly. The distance and angular
 measurements were verified as shown on the map and monumented as
 shown.

Basis of bearings--Recorded Survey No. 2189.

July 22, 1971



J. A. Hoffbuhr
 Registered Land Surveyor