

Survey No. \_\_\_\_\_

4663

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250,  
REVISED BY CHAPTER 555, O.L. 1963

FOR: BOISE CASCADE CORPORATION  
P. O. BOX 100, MEDFORD, OREGON

PURPOSE - To rehabilitate and perpetuate the one quarter section corner common to Sections 23 and 24, Township 32 South, Range 1 West, Willamette Meridian.

PROCEDURE - Found 1" iron pipe from which a 15" Douglas fir bears South  $34^{\circ}$  West a distance of 18.0' upper and lower faces closed and a 12" Douglas fir with closed faces which was knocked down by logging operations the stump hole of which bears North  $74^{\circ}$  East a distance of 5.9 feet. This agrees with Mark Boyden's 1955 establishment of the corner.

NEW REFERENCES - From the 1" iron pipe a 12" Douglas fir bears North  $69\frac{1}{2}^{\circ}$  East a distance of 26.7' scribed  $\frac{1}{4}$  S 24 in the upper face and BT in the lower face. The distance to the new bearing tree was measured to the face of the blaze and compass variation was set at  $20^{\circ} 00'$  East.

Field work was completed on October 6, 1971 by R. Morris and S. Richardson.

