

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Boise Cascade Corporation  
P. O. Box 100  
Medford, Oregon 97501

PURPOSE: To rehabilitate and perpetuate the 1/4 corner common to Sections 12 and 13, Township 31 South, Range 2 East W.M.

PROCEDURE: Found a cedar stump with visible scribe. No evidence of the other bearing tree or the original stone. At the record bearing and distance from the remaining original bearing tree set a 1" x 36" galvanized iron pipe, 30" in the ground, capped with a 1 1/2" to 1" bell reducer filled with pot metal and stamped as shown below:

R E 7122  
1/4  
12  
13  
T31S R2E  
1971

From which a 15" cedar bears N 51 1/2° E a distance of 141.1 feet scribed 1/4 S 12 - BT and a 10" Douglas fir bears S 49° E a distance of 72.7 feet scribed 1/4 S 13 - BT.

All distances and bearings were taken to the face of the upper blaze. Magnetic declination was set at 18° 30' East to agree with a solar observation taken nearby.

November 16, 1971

