

4750

4750

SURVEY FOR HUGH SWAFFORD
 SE 1/4 SEC. 24, T. 35 S., R. 2 W., W.M.
 JACKSON COUNTY, OREGON

April 27, 1971

O.S.H.D.
3/4" R./W. PIN



O.S.H.D.
3/4" R./W. PIN
1/2" I. PIN
0.87

OREGON HIGHWAY 234
 N 61° 23' E
 316.00

158.50

S 15° 58' 40" E
 225.00

27.08
 S 74° 01' 20" W

S 29° 25' 35" E
 858.08

858.08

(Rec. S 29° 00' E 850.30)

S 9° 06' 50" E
 556.42

845.96

(Rec. N 0° 14' E 970.88)

S 0° 17' 45" E 974.66

N 80° 53' 10" E
 19.72

128.70

1/2" I. PIN

SCALE 1" = 100'

BASIS OF BEARING:
 UNRECORDED PLAT REC. FOR
 HIGHWAY 234

LEGEND

- 5/8" x 24" Iron Pin Set
- Monument Found



REGISTERED
 OREGON
 LAND SURVEYOR

Verlyn Thomas

MAY 22, 1960
 VERLYN THOMAS
 505

SURVEY BY VERLYN THOMAS, PROFESSIONAL LAND SURVEYOR, MEDFORD, OREGON

23 | 24
 26 | 25 REC. EAST

1613.12
 3975.0

4750

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250
REVISED BY CHAPTER 555, O.L. 1963

FOR: Hugh Swafford
3795 Highway 234
Central Point, Oregon

PURPOSE: To create a new division line between properties, as directed
by client.

PROCEDURE:

Research produced a plat of an unrecorded survey by Hugh Ingle, dated October, 1959. The aforementioned division line is located in Tract "A" of this unrecorded survey. Original monuments recovered are shown on the accompanying plat, with dimensions as shown on the unrecorded plat. No attempt was made to verify the location of these original monuments relative to the section corner common to Sections 23, 24, 25 and 26.

The northeasterly corner of Tract "A" was reset at record from the northwesterly corner, and the new division line monumented as shown.

