

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250
REVISED BY CHAPTER 555. O.L. 1963

FOR: Jackson County Surveyor
Court House
Medford, Oregon

PURPOSE: To correct an error in procedure in performing Recorded Survey
No. 4166.

PROCEDURE:

It was recently brought to the attention of this surveyor that the center-north one sixteenth corner of Section 2, Township 36 South, Range 1 West, as established in said Recorded Survey No. 4166, had been set on a proportion based on the North half of said Section being originally described as 40 chains on either end. In fact, however, the West end of said North half was originally described as being 40.11 chains long.

The monument for the center-north one sixteenth corner was therefor moved South $0^{\circ} 14' 40''$ East, 1.83 feet to conform to a proper proportion, resulting in a distance of 1334.60 feet to the North one quarter corner of said Section 2.

Said monument moved November 13, 1971, assisted by Gary Kaiser,
L.S. 803.

