

MAP OF SURVEY
 LOCATED IN
 LOT 1, BLOCK 26 OF THE "CITY OF ASHLAND"
 JACKSON COUNTY OREGON
 FOR

FRED TAYLER

EVERETT L. SWAIN, R.L.S. ASHLAND, OREGON
 SCALE: 1" = 50'
 BASIS OF BEARING U.S.C. & G.S. TRUE BEARING
 • SET 3/8 INCH IRON PIN TAGGED RLS 759


NORTH

FD. 1" IRON BAR
 10-12" DEEP

SET 2" x 24" GI PIPE
 PER "CITY OF ASHLAND"
 R.P.'S
 R/S 4702

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Everett L. Swain
 OREGON
 JULY 8, 1933
 EVERETT L. SWAIN
 759



- | | | |
|---|--|--|
| 1. FD. 1/2" G.I. PIPE
S. 0.53'
E. 0.49' | 3. FD. 1/2" PIPE
N. 0.31'
E. 0.21' | 5. FD. 3/4" PIPE
N. 0.54'
W. 0.01' |
| 2. FD. 1/2" PIPE
S. 0.35'
E. 0.33' | 4. FD. 1/2" PIPE
S. 0.44'
E. 0.54' | 6. FD. 1" I.P.M.
N. 0.57'
E. 0.22' |

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Fred Tayler
137 North Main
Ashland, Oregon 97520

LOCATION: Situated in Lot 1, Block 26 of the "City of Ashland",
Jackson County, Oregon.

PURPOSE: To survey and partition Lot 1 of Block 26, as shown on
the accompanying map, per clients request.

PROCEDURE: From survey control previously established by this office,
proceeded to proportion the position of the alley in
Block 26, in relation to the information shown on the
official "City of Ashland" survey map, dated November
5, 1888. With the position of the alley established,
proportioned the Southeasterly boundary of Lot 1,
Block 26 as shown on the accompanying map. With this
boundary established proceeded to survey the tracts as
shown.

January 7, 1972

Everett L. Swain
Professional Land Surveyor
Ashland, Oregon

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Everett L. Swain

OREGON
JULY 8, 1966
EVERETT L. SWAIN
759

JACKSON COUNTY
RECORDED
MAR 3 1972
SURVEYOR