



Survey No. - 4820

Survey Narrative to Comply With O.R.S. 209.250

FOR: Glenn Nelson and  
Michael Kaiser  
Eagle Point, Oregon

PURPOSE: (1) To monument tract described in Instrument No. 70-09688 located in Section 2, Township 36 South, Range 1 West of the Willamette Meridian in Jackson County, Oregon.

(2) To monument and describe a 5.00 acre parcel lying south of the tract described in Instrument No. 70-09688, East of the Ingress and Egress easement described in Instrument No. 72-00407 and West from the water line easement described in deed volume 336, Page 259.

PROCEDURE: Began random traverse at the Northwest corner to Section 2 and traversed around the Northwest Quarter of Section 2 tying in the control corners (the Northwest corner, West  $\frac{1}{4}$  corner and North  $\frac{1}{4}$  corner have been re-established by the County Surveyor, the center  $\frac{1}{2}$  corner was established on recorded survey No. 4166 and the center-North  $\frac{1}{16}$  corner was established as per recorded survey narrative No. 4765). After tying in control corners traversed around and monumented two parcels as shown on the map accompanying this narrative. Bearings are based on the "Eastwest" centerline of Section 2 between the West  $\frac{1}{4}$  corner and the center  $\frac{1}{2}$  corner as per recorded Survey No. 4166.

March 13, 1972

