

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Boise Cascade Corporation
P. O. Box 100
Medford, Oregon 97501

PURPOSE: To rehabilitate and perpetuate the one quarter section corner common to Sections 34 and 35, Township 32 South, Range 3 East, Willamette Meridian.

PROCEDURE: Found a dying 21" Douglas fir with visible scribe and an old stump showing the lower portion of an old face of approximately the right age which agrees quite closely with the original notes for the Section 35 bearing tree. The original stone was also present but it was dislodged from its original position. At the intersection of the record distances from the two trees set a 1" x 36" galvanized iron pipe 32" in the ground capped with a 1½" to 1" bell reducer filled with pot metal and stamped as shown below:

RE 7122
¼
34|35
T32S R3E
1972

From which:

a 18" cedar bears N 66° W a distance of 34.7 feet, scribed
¼ S 34 - BT

a 9" Douglas fir bears S 42° E a distance of 71.2 feet, scribed
¼ S 35 - BT

All distances and bearings were taken to the face of the upper blaze and magnetic declination was set at 20° East.

Field work was completed on July 26, 1972 by R. Morris and J. Gartman.

