

N.W. Cor. D.L.C. 40
fd. 1" iron pipe

N 89° 49' 32" W

1134.90

N.E. Cor. D.L.C. 40
fd. 2" iron pipe w/3" br. cap

S 0° 04' 55" W
607.35

(Rec. N 0° 03' E)

STREET

S 89° 55' 05" E
105.00

30'

30'

95.00

N 89° 55' 05" W
105.00

S 0° 04' 55" W
95.00

N 0° 04' 55" E

LAUREL

fd. 3/4" iron pipe (12" deep)
at centerline of Orange St.



SCALE 1" = 50'

Basis of Bearings: Rec. Survey 4837

- = Set 5/8" x 30" iron pin tagged R.L.S. 638
- = Found monument as shown



REGISTERED
PROFESSIONAL
LAND SURVEYOR

George Burrell

OREGON
JULY 10, 1964
GEORGE R. BURRELL
638

Map of Survey

Located in D.L.C. No. 40, Twp 39S, R1E W.M. J.C.O.
For: CHARLES LOCKRIDGE ASHLAND, OREGON
By: George Burrell Surveyor July 1972

82

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Charles Lockridge
265 Orange St.
Ashland, Oregon

PURPOSE: To monument and describe the tract as shown on the
accompanying map.

PROCEDURE: The control monuments of Recorded Survey No. 4837
were used for determining the tie to the Northeast
Corner of D.L.C. No. 40.
The Centerline of Laurel Street was established by
turning the record angle at the monument on Orange
and Laurel Streets, from the monument at the center-
line of Orange and Willow Streets. The latter monu-
ment was destroyed by street construction previous
to this survey and the original position is now
based on a coordinate tie made before its destruction.

