



JACKSON COUNTY
RECORDED
SEP 28 1972

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edward A. McGinty

OREGON
JULY 10, 1953
EDWARD A. MCGINTY
33001

SURVEY IN SEC 29, T 35S RIW WM
JAMES LUCE &
PAT VONDERHELLEN

72-16

EDWARD A. MCGINTY
MEDFORD OREGON
APRIL 1972

SCALE 1" = 200'
o SET 5/8" I. PIN
q WIT. COR.

S 1/4 COR.

N 1/4 COR.

Survey No. 4949

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209-250

Survey for: Dr. James C. Luce
Mrs. Pat Von der hellen
Agate Rd.
Eagle Point, Oregon

Survey by: Edward A. McGinty, R.S.
Medford, Oregon
April, 1972

Basis of Bearing: Survey No. 3434

Precedence of Survey:

Surveyed the North and South center line of Section 29 and thru the utilization of previous surveys 2426, 2776, 1692 and using survey No. 4692 as a cross check, partially sub-divided the southwest 1/4 to determine the 1/16 corner.

The south center 1/16 corner fell on a large rock outcrop. At this point chiseled and X setting a witness corner westerly 4.49 ft. Monuments found at the North 1/4 corner and the south 1/4 corner, being est. by the county surveyor.

Corners and witness corners set being 5/8 in. x 24 in. iron pins, set approx. flush with the surface.

72-16

