

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Boise Cascade Corporation
P. O. Box 100
Medford, Oregon 97501

PURPOSE: To rehabilitate and perpetuate the one quarter section corner common to Sections 12 and 13, Township 32 South, Range 1 West, Willamette Meridian.

PROCEDURE: Found a badly damaged 18" Douglas fir, with visible scribe, for the Southeast bearing tree and a 17" Douglas fir with healed over face for the Northeast bearing tree. This bearing tree had been hit by a large boulder which changed its location slightly. Did not find the original corner stone. At the record distance and bearing from the Southeast bearing tree set a 1" x 36" galvanized iron pipe 34" in the ground, capped with a 1 1/2" to 1" bell reducer filled with pot metal and stamped as shown below

RE 7122
1/4
12
13
T32S R1W
1972

From which:

a 13" Douglas fir bears S 33° E a distance of 71.0 feet, scribed
1/4 S 13 - BT

a 18" Douglas fir bears N 18° W a distance of 110.2 feet, scribed
1/4 S 12 - BT

All distances and bearings were taken to the face of the upper blaze and magnetic declination was set at 20° East.

Field work was completed on November 1, 1972 by R. Morris and D. Applebaker.

