



JACKSON COUNTY
RECORDED
DEC 21 1972
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Edward A. McGinty
OREGON
JULY 10, 1983
EDWARD A. MCGINTY
301

SURVEY IN S 1/2 SEC. 2, N 1/2 SEC. 11 T. 36 S. R. 1 W. W.M.
FOR
VETERANS ADMINISTRATION
72-42

EDWARD A. MCGINTY
MEDFORD, OREGON
OCTOBER, 1972

SCALE = 1" = 100'
○ 5/8" IRON PIN (SET)
● 5/8" IRON PIN (FOUND)
⊠ CONCRETE MONUMENT

D

SURVEY NARRATIVE TO COMPLY WITH ORS. 209-250

Survey for: Veterans Administration 72-42
 White City, Oregon
 (Mr. Beal)

Survey by: Edward A. McGinty, R.S.
 Medford, Oregon
 October, 1972

Basis of Bearing: Survey No. 4914

Location of Survey: South 1/2 of Sec. 2 and the North 1/2 of Sec. 11
 T.36 S., R. 1 W. WM.

PRECEDENCE OF Survey:

This survey is a dependant survey of previous surveys by the U.S. Engineers, Survey No. 4914 and 2705 and the county road datum.

The county road was determined from a spike found and hub at the P.I. with the exception of P.I. curve radius 716.20 feet, which was set from a 2 in. county reference points (note; PI replaced with iron pins).

Note previous survey No. 4166 indicates a small difference of location of some of the corners previously set by the U.S. Engineers - see Narrative of survey No. 4914.

- A. Found conc. mon., now 0.04 ft. north of line extended easterly (note: recent indications of a tractor scapping the top in making fire protection trail).
- B. Found conc. mon., mk. Lot 12.
- C. Found conc. mon., apparently slightly east of line with 1/4 cor. and Pt. D.
- D. Found conc. mon. mk. S C 1/16 US Eng., 1942.
- E. Found conc. mon. mk. S W 1/16 US Eng. 1942.
- F. Found 5/8 in. iron pin, apparently an unrecorded survey.
- F - G, line depending on survey No. 2705.
- H. Found conc. mon. Mk. N C 1/16 US Engr. 1942
- I. Found conc. mon. Mk. NE 1/16 US Engr. 1942

All conc. monuments found were brass disc. 6 x 6 in., 6 ins. high.

Monument s set being 5/8 in. iron pins.

